


● Key-LOK Lift Insert Capacity



STANDARD
REINFORCEMENT

U-SHAPE
REINFORCEMENT

LI-1098B
3-1/2" Wall

1,200
POUNDS / INSERT

2,000
POUNDS / INSERT

LI-1096B
4-1/2" Wall

2,000
POUNDS / INSERT

3,400
POUNDS / INSERT

LI-1095A
Wet Cast 5" Wall
LI-1095B
Dry Cast 5" Wall

3,000
POUNDS / INSERT

4,500
POUNDS / INSERT

LI-1097A
Wet Cast 6" or 7" Wall
LI-1097B
Dry Cast 6" or 7" Wall

3,600
POUNDS / INSERT

6,500
POUNDS / INSERT

LI-1095BR
Cam-LOK Insert
Wet Cast 5" Wall

3,000
POUNDS / INSERT

4,500
POUNDS / INSERT

